



KERALA STATE ELECTRICITY BOARD LIMITED

(Incorporated under the Indian Companies Act, 1956)

Reg.Office: Vidyuthi Bhavanam, Pattom, Thiruvananthapuram - 695 004

CIN :U40100KL2011SGC027424, Website: www.kseb.in

Phone: +91 471 2514576, 2446885, 9446008884, E-mail: dtkseb@kseb.in

ABSTRACT

Power Evacuation from proposed 50MW Solar Park at Paivalike to 110kV Substation, Kubanoor - Technical Sanction - accorded - orders issued.

Corporate Office(SBU-T)

B.O.(FTD)No.824/2019/D(T,SO&S)/T6/Paivalikae/2019-20 dated Thiruvananthapuram 6.11.2019

Read : 1.B.O(FTD) No.698/2019/D(T,SO&S)/T6/Paivalike/2019-20 dtd 19.9.2019

2. Letter No. CE/TRN/E2/Solar Paivelika/2019-20/1050 dtd 1.11.2019 of the Chief Engineer (Transmission North)

3. Note No. D(T,SO&S)/T6/Paivalikae/2019-20/70 dated 1.11.2019 of the Director(T,SO&S) to the Full Time Directors (Agenda : 19/11/2019)

ORDER

Administrative Sanction had been accorded as per order read 1 abovefor the power evacuation proposal at the 50MW Solar Park at Paivalikae to 110kV Substation, Kubanoor under Transmission Circle, Kannur, which involves the following works :

A. Construction of 3 Nos. of 33kV feeder bays & installation of 3 Nos. of 25 MVA 110/33kV Transformers and construction of associated 110kV and 33 kV bays at 110kV Substation, Kubanoor (Transmission Development works) at an estimated of cost of Rs.12,00,00,000/-

AND

B. Laying 3 run 8.5 km 33 kV 3x400 mm² XLPE cable from Solar Park, Paivalike to 110KV Substation Kubanoor at an estimated of cost of Rs.12,90,00,000/-,to be carried out on turn key basis, by KSEBL on payment by RPCKL (Deposit work).

Also, the Chief Engineer (Transmission North) was directed to undertake the tendering and execution of the evacuation work as above, on warfoot basis, so as to complete the work latest by March 2020, in synchronisation with the completion of the Solar Power Park.

As per MNRE guideline, Part A of the subject is to be carried out by KSEBL and Part B by RPCKL. The Chief Engineer (Transmission North) vide note read 2 above has requested to accord Technical Sanction for Part B of the subject work as the same is above the sanctioned limit for Deposit Work, of that office. Further, it was requested to ratify the action of issuing sanction for working estimate of Part B of the work, as sanction was accorded by Chief Engineer (Transmission North) to speed up the tendering work, considering the urgency of the work.

Having considered the above, the Full Time Directors, in the meeting held on 2.11.2019 RESOLVED to grant consent for according Technical Sanction for the estimate amounting to Rs.12.9 cr. (Rupees twelve crore ninety lakh only) for the deposit work of supplying, laying, testing and commissioning 3 run 8.5 km 33 kV 3x400 mm² XLPE Cable from the proposed solar park at Paivalike to 110KV Substation, Kubanoor, as turnkey project, on payment by RPCKL.

Orders are issued accordingly.

By Order of the Full Time Directors,

sd/-

Lekha G.

Company Secretary (In- Charge)

To :

The Chief Engineer (Transmission North)

Copy to:

The Deputy Chief Engineer (Transmission Circle, Kannur)

The Deputy Chief Engineer (IT)

The Financial Adviser/ The Chief Internal Auditor.


The RCAO/ RAO.

The TA to Chairman & MD/ D(T&SO)/ D(D & IT)/ D(G-C&HRM)/ D(CP,G-E, SCM&S)

The PA to Director (Finance)/CA to Company Secretary

Fair Copy Superintendent/Library/Stock File.

Forwarded / By Order


Assistant Executive Engineer