



KERALA STATE ELECTRICITY BOARD LIMITED

(Incorporated under Companies Act, 1956)

CIN:U40100KL2011SGC027424

Reg. Office: Vydyuthi Bhavanam, Pattom, Thiruvananthapuram- 695 004, Kerala.

Phone: +91 471 2514685, 2514331, Fax: 0471 2447228

website: www.kseb.in E-mail: ddkseb@kseb.in

ABSTRACT

Uniform Labour Data- Inadequate rate for work item-"Adding one conductor for street mains" - revision of Labour data - Sanctioned - Orders issued.

CORPORATE OFFICE (SBU-D)

B.O (FTD) No. 468/2020 (D (D&IT)/D6-AE3/ULD 2018 /2019-20) dated, Tvpn 09.07.2020

Read: 1 KSERC OA No.17 of 2017 dated 27.04.2018.

2. BO (FTD) No.1189/2018(D (D&IT)/D6-AE3/ULD/2018) dated 07.05.2018.
3. Circular No.D (D&IT)/D6-AE3/ULD/2018 dated 04.06.2018.
4. Letter No. DCE/DIST/KNR/TS3/2020-21/123 dated 09.06.2020 of Deputy Chief Engineer, Electrical Circle, Kannur.
5. Note No. D (D&IT)/D6-AE3/ULD 2018/2019-20 dated 23.06.2020 of the Director (Distribution , IT&HRM) to the Full Time Directors (Agenda 1/7/20).

ORDER

The Deputy Chief Engineer, Electrical Circle, Kannur as per letter read as 3rd above, has reported that there are ongoing deposit works under LAC-ADS and as well as request from LSGD for street main adding and these works are being delayed as the contractors are unwilling to carry out the work as per the prevailing rates stating that they are inadequate for the labour involved. With the elections of the Local Bodies fast approaching, carrying out the Deposit works for which funds have already been received is highly inevitable, and these works need to be completed in a time bound manner.

It has also been reported that in addition to the above, a project has been sanctioned under RURBAN scheme in the Phase III Rurban Cluster belonging to Pinarayi- Vengad of Kannur district. The project comprises of street main extension to the extent of around 200km and providing LED Street lights in the villages of Pinarayi and Vengad under Electrical Sections of Pinarayi, Vengad, Kathirur and Chakkarakkal amounting to Rs.406 lakhs. The concerned LSGD will shortly remit the amount and the work will have to be executed before the local body elections.

The Deputy Chief Engineer, EC Kannur, as per letter read as 4th above, has requested that item 428, as per the ULD 2018, "*Stringing, shackling, fitting insulators (excluding fitting of cross arm)*

and binding, giving jumper connection etc. for one km additional conductor (ACSR Weasel) on existing LT line (where relocation of one existing conductor is also required) including cutting and removing tree branches wherever necessary and conveyance of all materials (except poles) from stacking place” is most appropriate for adding street main, compared to item 219 of ULD 2018.KSEBL has already proposed the use of ACSR Rabbit instead of Weasel conductor as per order read as 1 above, considering its higher mechanical strength and scope for future expansion. Hence the Deputy Chief Engineer, Electrical Circle Kannur has reported that the item 428 (using Weasel) is inadequate and requested to provide the rate for new item of work using ACSR Rabbit, which can be used for drawing street mains.

Based on the discussion with field officers, the Director (Distribution, IT &HRM) as per note read as 5th above, has suggested a proposal for data estimation for new item using ACSR Rabbit (in line with ULD 2018 labour data for item no 428),which is far below than that approved by the KSERC.

It is also suggested that it would be appropriate to sanction a uniform rate although the BO read as 2nd states that the rates for works which are not included in the Uniform Labour data at present are to be approved by the concerned Executive Engineer/ Deputy Chief Engineer and hence the matter is placed before the Full Time Directors for a decision.

Having considered the matter in detail, the Full Time Directors of the Board in its meeting held on 02.07.2020, resolved to approve the data estimation for new item using ACSR Rabbit (in line with ULD 2018 Labour Data for item No.428) as proposed in Annexure.

Further resolved to accord sanction to include the above approved rate in ULD 2018, as new item No.430.

Further resolved to entrust the Chief Engineer (IT &CR) to include the new item in Work Express.

Orders are issued accordingly.

By Order of the Full Time Directors
sd/-
Lekha.G
Company Secretary-in charge.

To

The Chief Engineers, Distribution.
The Deputy Chief Engineers, Distribution.
The Chief Engineer (IT, CR&CAPS).

Copy to:

The Chief Vigilance Officer/Legal Advisor &Disciplinary Enquiry Officer/ Chief Internal Auditor

The TA to Chairman & Managing Director

The TA to Director (Distribution, IT& HRM / Planning & Safety/ Generation- Electrical, &SCM / Transmission & System Operation, REES / Generation- Civil)

The Deputy Chief Engineer (Commercial & Planning) with full powers of Chief Engineer

The RAO/ECA/RCAO/The Legal Liaison Officer

The PA to Director (Finance) / C.A. to Secretary (Administration)/ Company Secretary

Fair Copy Section / Library / Stock File

Forwarded / By Order

Resmi R

Assistant Engineer

**Annexure to B.O (FTD) No. 468/2020 (D (D&IT)/D6-AE3/ULD 2018 /2019-20) dated Tvpm,
09.07.2020.**

Data for Stringing one km LT Additional conductor (Rabbit) after relocating one of the existing conductors, incl. fitting insulators, removing touchings and conveyance of materials.					
Sl No	Qty	Description	Unit	Labour rate (as approved in ULD 2018)	Amount in Rs.
		Stringing, shackling, fitting insulators (excluding fitting of cross arm) and binding, giving jumper connection etc. for one km additional conductor (ACSR Rabbit) on existing LT line (where relocation of one existing conductor is also required) including cutting and removing tree branches wherever necessary and conveyance of all materials (except poles) from stacking place	km		
i	0.875	Lineman	Each	638.58	558.75
ii	1	Lineman(A)[Mate]	Each	525.71	525.71
iii	4.5	Special Mazdoor[Stone breaker]	Each	581.43	2616.43
iv	3.375	Mazdoor[Khalasi]	Each	525.71	1774.28
v		Labour rate			5475.13
vi		Add 10% Contractor's profit			547.51
		Total Labour rate			6022.64
Total Amount applicable for new item as per ULD 2018 rates					6023
Rate per Kilometer(rounded to)					Rs. 6025